

Date: Wednesday, 5/23/2007 3:44:27 PM
User: Kim Johnston

Process Sheet

Customer	: CU-DAR001	Dart Helicopters Services	Drawing Name	: HELI ACCESS STEP EXT HIGH GEAR
Job Number	: 32508			
Estimate Number	: 12874			
P.O. Number	: N/A		Part Number	: D205633025
This Issue	: 5/23/2007	S.O. No. : N/A	Drawing Number	: DSI 9300 REV B
Prsht Rev.	: NC		Project Number	: N/A
First Issue	: N/A	Type : LARGE FAB ASSY	Drawing Revision	: B
Previous Run	: N/A		Material	: N/A
Written By	:		Due Date	: 6/10/2007
Checked & Approved By	:		Qty:	2 Um: Each
Comment	:			
	:	Est Rev: B		
	:	Added D3165-1		
	:	KJ/JLM		
	:	05-09-09		

Additional Product

Job Number:

Seq. #:	Machine Or Operation:	Description :
---------	-----------------------	---------------

1.0 DC DOCUMENT CONTROL

Comment: DOCUMENT CONTROL

Photocopy bluefile & type labels per PPPD205-633-025

CHG001

KS 07.05.30

2.0	PACKAGING 1	PACKAGING RESOURCE #1
-----	-------------	-----------------------

Comment: PACKAGING RESOURCE #1

Pick Packing Kit

3.0	D2022101	Spacer	
-----	----------	--------	--

Comment: Qty.: 4.0000 Each(s)/Unit Total : 8.0000 Each(s)

Spacer

Batch:

B30543

4.0 D2022103 Spacer

Comment: Qty.: 2.0000 Each(s)/Unit Total : 4.0000 Each(s)

Spacer

Batch:

B5967v

5.0	D2562005	Strut	
-----	----------	-------	--

Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Strut

Batch#

~~B32459~~ B32875

7/6/8 SP

W/O:		WORK ORDER CHANGES							
DATE	STEP	PROCEDURE CHANGE		By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector	

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)							
DATE	STEP	Description of NC Section A	Corrective Action			Verification Section C	Approval Chief Eng	Approval QC Inspector	
			Initial Chief Eng	Action Description Chief Eng	Sign & Date				

NOTE: Date & initial all entries

Date: Wednesday, 5/23/2007 3:44:28 PM
User: Kim Johnston

Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: HELI ACCESS STEP EXT HIGH GEAR

Job Number: 32508

Part Number: D205633025

Job Number:



Seq. #:

Machine Or Operation:

Description :

6.0

D2563

Step Weldment Assembly



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Step Weldment Assembly

Batch:

332388A ✓

7.0

D31651

Support Arm



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Support Arm

Batch:

323322 ✓

8.0

D2565301

Strut



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Strut

Batch:

326639 ✓

9.0

D2565303

Strut



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Strut

Batch:

326640 ✓

10.0

D2565305

Strut



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Strut

Batch:

326641 ✓

11.0

D2565307

Strut



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Strut

Batch:

326642 ✓

12.0

D2565309

Strut



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Strut

Batch:

326643 ✓

7/6/8 S9

W/O:		WORK ORDER CHANGES						
DATE	STEP	PROCEDURE CHANGE		By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)							
DATE	STEP	Description of NC Section A	Corrective Action		Section B		Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng		Sign & Date			

NOTE: Date & initial all entries

Date: Wednesday, 5/23/2007 3:44:28 PM
User: Kim Johnston

Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: HELI ACCESS STEP EXT HIGH GEAR

Job Number: 32508

Part Number: D205633025

Job Number:



Seq. #:

Machine Or Operation:

Description :

13.0

D3437045

Aft Strut Assembly



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Aft Strut Assembly

Batch: ~~B32595~~ B32590

14.0

AN45A

Bolt



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Bolt

Batch: M100857 ✓

15.0

AN46A

Bolt



Comment: Qty.: 3.0000 Each(s)/Unit Total : 6.0000 Each(s)

Bolt

Batch: M103962 ✓

16.0

AN47A

Bolt



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Bolt

Batch: M16149 ✓

17.0

AN412A

Bolt



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Bolt

Batch: M103947 ✓

18.0

AN414A

Bolt



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Bolt

Batch: M102473 ✓

19.0

AN447A

BOLT



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

BOLT

Batch: M14781 ✓

2/6/8 50

W/O:		WORK ORDER CHANGES						
DATE	STEP	PROCEDURE CHANGE		By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)							
DATE	STEP	Description of NC Section A	Corrective Action		Section B		Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng		Sign & Date			

NOTE: Date & initial all entries

Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: HELI ACCESS STEP EXT HIGH GEAR

Job Number: 32508

Part Number: D205633025

Job Number:



Seq. #:

Machine Or Operation:

Description :

20.0

AN514A

Bolt



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Bolt

Batch: M101291 ✓

21.0

AN514A

Bolt



Comment: Qty.: 1.0000 Each(s)/Unit Total : 2.0000 Each(s)

Bolt

Batch:

N/A 4/17/07-09

22.0

AN960JD416

Washer



Comment: Qty.: 14.0000 Each(s)/Unit Total : 28.0000 Each(s)

Washer

Batch: M103691 ✓

23.0

AN960JD516

Washer



Comment: Qty.: 3.0000 Each(s)/Unit Total : 6.0000 Each(s)

Washer

Batch: M103641 ✓

24.0

MS21042L4

Nut



Comment: Qty.: 7.0000 Each(s)/Unit Total : 14.0000 Each(s)

Nut

Batch: M102552 ✓

25.0

MS21042L5

Nut



Comment: Qty.: 2.0000 Each(s)/Unit Total : 4.0000 Each(s)

Nut

M102536

SP 7/4/8

26.0

QC4

INSPECT 100% KITS FOR COMPLETENESS



Comment: INSPECT 100% KITS FOR COMPLETENESS

PC 7/7/6

C207107106 ②

W/O:		WORK ORDER CHANGES						
DATE	STEP	PROCEDURE CHANGE		By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: 2 Date: 07/07/06
 QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)							
DATE	STEP	Description of NC Section A	Corrective Action		Section B		Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng		Sign & Date			

NOTE: Date & initial all entries

Date: Wednesday, 5/23/2007 3:44:28 PM
User: Kim Johnston

Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: HELI ACCESS STEP EXT HIGH GEAR

Job Number: 32508

Part Number: D205633025

Job Number:



Seq. #:

Machine Or Operation:

Description :

27.0

PACKAGING 1

PACKAGING RESOURCE #1



Comment: PACKAGING RESOURCE #1

Identify and pack for shipping as per PPP D205-633-025

Location:

PPP Rev:

Draft

Eff 5/23/07/0421

28.0

QC21

FINAL INSPECTION/W/O RELEASE



(2)

Comment: FINAL INSPECTION/W/O RELEASE

Draft 5/23/06

Job Completion



UAF-87-06

W/O:		WORK ORDER CHANGES						
DATE	STEP	PROCEDURE CHANGE		By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector



Part No: _____ PAR #: _____ Fault Category: _____ NCR: Yes No DQA: _____ Date: _____

QA: N/C Closed: _____ Date: _____

NCR:		WORK ORDER NON-CONFORMANCE (NCR)							
DATE	STEP	Description of NC Section A	Corrective Action		Section B		Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date				

NOTE: Date & initial all entries

DART

DESIGN RF	DRAWN BY RF	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED 	APPROVED 	DRAWING NO. DSI 9300	REV. B SHEET 1 OF 6
DATE 05.08.12		TITLE SIMPLEX TANK STEP	SCALE NTS
A	05.05.05	NEW ISSUE	
B	05.08.12	ADD STRUTS IF TANK REMOVED	

DART SERVICE INSTRUCTION

TO AMEND INSTALLATION INSTRUCTIONS IIN-D205-633 REV. A

REF. CANADIAN STC: SH96-57

REF. FAA STC: SR00592NY, SR00593NY, SR00594NY

THE PURPOSE OF THIS SERVICE INSTRUCTION IS TO ADD THE D205-633-021/-022/-023/-024/-025/-026 STEPS TO ADDRESS COMPATABILITY WITH THE SIMPLEX MODEL 304 FIRE ATTACK TANK. D205-633-021/-022 ARE IDENTICAL TO D205-633-011, EXCEPT AS SHOWN HERE. D205-633-023/-024 ARE IDENTICAL TO D205-633-013, EXCEPT AS SHOWN HERE. D205-633-025/-026 ARE IDENTICAL TO D205-633-015, EXCEPT AS SHOWN HERE.

NOTE THAT THE STRUTS REQUIRED TO INSTALL THE STEPS ON THE LOWER AFT HARDPOINT HAVE ALSO BEEN INCLUDED WITH THE KITS IN CASE THE TANK IS REMOVED FOR ANY REASON. THESE STRUTS SHOULD BE INSTALLED I.A.W. IIN-D205-633, EXCEPT REPLACE EYEBOLT WITH AN4 BOLT ON LOWER HARDPOINT. ALSO NOTE THAT IF THE THREADS PROTRUDE THROUGH THE BAR ON THE D3437-XXX STRUT ASSEMBLIES AFTER ADJUSTMENT THEY MAY BE TRIMMED OFF.

WEIGHT AND BALANCE

Installation	Weight	LATERAL		LONGITUDINAL	
		Arm	Moment	Arm	Moment
D205-633-021 HELI-ACCESS-STEP™	14.0 lb 6.35 kg	-50.0 in -1.27 m	-700 in lb -8.06 m kg	94.5 in 2.40 m	1323 in lb 15.24 m kg
D205-633-022 HELI-ACCESS-STEP™	13.2 lb 6.00 kg	+50.0 in +1.27 m	+660 in lb +7.62 m kg	94.5 in 2.40 m	1247 in lb 14.40 m kg
D205-633-023 HELI-ACCESS-STEP™	14.3 lb 6.50 kg	-50.0 in -1.27 m	-715 in lb -8.26 m kg	94.5 in 2.40 m	1351 in lb 15.6 m kg
D205-633-024 HELI-ACCESS-STEP™	13.5 lb 6.14 kg	+50.0 in +1.27 m	+675 in lb +7.80 m kg	94.5 in 2.40 m	1276 in lb 14.74 m kg
D205-633-025 HELI-ACCESS-STEP™	14.6 lb 6.64 kg	-50.0 in -1.27 m	-730 in-lb -8.43 m-kG	94.5 in 2.40 m	1380 in-lb 15.94 m-kG
D205-633-026 HELI-ACCESS-STEP™	13.8 lb 6.27 kg	+50.0 in +1.27 m	+690 in-lb +7.96 m-kG	94.5 in 2.40 m	1304 in-lb 15.05 m-kG

SHOP COPY
RETURN TO
ENGINEERING
UNCONTROLLED COPY
SUBJECT TO AMENDMENT
WITHOUT NOTICE
WORK ORDER
NO. 32508

CANADA
DEPARTMENT OF TRANSPORT
AIRCRAFT CERTIFICATION
BRANCH
DAO # 01-O-01

APPROVED

BY: 
D. SHEPHERD (DE # 02)

DATE: 05.08.12
CERT. NO.: SH96-57
ISSUE NO.: #5

Copyright © 2005 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.



DESIGN RF	DRAWN BY RF	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED 	APPROVED 	DRAWING NO. DSI 9300	REV. B SHEET 2 OF 6
DATE 05.08.12		TITLE SIMPLEX TANK STEP	SCALE NTS

PARTS LIST

QTY -021	QTY -022	QTY -023	QTY -024	QTY -025	QTY -026	Part Number	Description
X						D205-633-021	Hell-Access-Step™ (LH), High Gear
	X					D205-633-022	Hell-Access-Step™ (RH), High Gear
		X				D205-633-023	Hell-Access-Step™ (LH), Extended High Gear (31")
			X			D205-633-024	Hell-Access-Step™ (RH), Extended High Gear (31")
				X		D205-633-025	Hell-Access-Step™ (LH), Extended High Gear (39")
					X	D205-633-026	Hell-Access-Step™ (RH), Extended High Gear (39")
4	4	4	4	4	4	D2022-101	SPACER
2	2	2	2	2	2	D2022-103	SPACER
				1	1	D2562-005	STRUT
1	1					D2562-011	STRUT
		1	1			D2562-013	STRUT
1		1		1		D2563	WELDMENT ASSEMBLY
				*1	*1	D3165-1	STRUT
1	1					D2565-101	STRUT
1	1					D2565-103	STRUT
1	1					D2565-105	STRUT
1	1					D2565-107	STRUT
1	1					D2565-109	STRUT
*1	*1					D2565-111	STRUT
		1	1			D2565-201	STRUT
		1	1			D2565-203	STRUT
		1	1			D2565-205	STRUT
		1	1			D2565-207	STRUT
		1	1			D2565-209	STRUT
		*1	*1			D2565-211	STRUT
				1	1	D2565-301	STRUT
				1	1	D2565-303	STRUT
				1	1	D2565-305	STRUT
				1	1	D2565-307	STRUT
				1	1	D2565-309	STRUT
1	1					D3437-041	AFT STRUT ASSEMBLY
		1	1			D3437-043	AFT STRUT ASSEMBLY
				1	1	D3437-045	AFT STRUT ASSEMBLY
	1		1		1	D3438-042	WELDMENT ASSEMBLY
1	1	1	1	1	1	AN4-5A	BOLT
4	4	3	3	3	3	AN4-6A	BOLT
1	1	1	1	1	1	AN4-7A	BOLT
1	1					AN4-11A	BOLT
		1	1	1	1	AN4-12A	BOLT
1	1	1	1	1	1	AN4-14A	BOLT
1	1	1	1	1	1	AN44-7A	EYEBOLT
1	1	1	1	1	1	AN5-14A	BOLT
16	16	14	14	14	14	AN960JD416	WASHER
3	3	3	3	3	3	AN960JD516	WASHER
8	8	7	7	7	7	MS21042L4	NUT (or MS21042-4)
2	2	2	2	2	2	MS21042L5	NUT (or MS21042-5)

* ONLY INSTALLED IF TANK IS REMOVED

CANADA DEPARTMENT OF TRANSPORT AIRCRAFT CERTIFICATION BRANCH DAO # 01-O-01		ENGINEERING CONTROLLED COPY SUBJECT TO AMENDMENT WITHOUT NOTICE WORK ORDER NO 32508
APPROVED BY: D. SHEPHERD (DE # 02)		
DATE:	05.08.12	
CERT. NO.:	SH96-57	
ISSUE NO.:	#5	

Copyright © 2005 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

DART


DESIGN RF	DRAWN BY RF	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED <i>[Signature]</i>	APPROVED <i>[Signature]</i>	DRAWING NO. DSI 9300	REV. B 3 OF 6
DATE 05.08.12		TITLE SIMPLEX TANK STEP KIT	SCALE NTS

INSTALLATION OF D205-633-021/-022/-023/-024/-025/-026

INSTALL D205-633-021/-022 AS PER THE D205-633-011 STEP OF INSTALLATION INSTRUCTIONS IIN-D205-633 REV.A, EXCEPT REPLACE D2565-111 STRUT WITH THE D3437-041 AFT STRUT ASS'Y, REMOVE D2562-001 STRUT, INSTALL D2562-011 STRUT AS SHOWN.

INSTALL D205-633-023/-024 AS PER THE D205-633-013 STEP OF INSTALLATION INSTRUCTIONS IIN-D205-633 REV.A, EXCEPT REPLACE D2565-211 STRUT WITH THE D3437-043 AFT STRUT ASS'Y, REMOVE D2562-003 STRUT, INSTALL D2562-013 STRUT AS SHOWN.


INSTALL D205-633-025/-026 AS PER THE D205-633-015 STEP OF INSTALLATION INSTRUCTIONS IIN-D205-633 REV.A, EXCEPT REPLACE D3165-1 SUPPORT ARM WITH THE D3437-045 AFT STRUT ASS'Y AS SHOWN.



D205-633-021/-023/-025 SHOWN.
D205-633-022/-024/-026 SIMILAR
(VIEW LOOKING DOWN)

AN44-7A EYEBOLT (1)
AN960JD516 WASHER (1)
MS21042L5 NUT (1)

DETAIL S
NOT TO SCALE



AN4-6A BOLT (1)
AN960JD416 WASHER (2)
MS21042L4 NUT (1)

SHOP COPY
RETURN TO
ENGINEERING
UNCONTROLLED COPY
SUBJECT TO AMENDMENT
WITHOUT NOTICE
WORK ORDER
NO. 32508

CANADA
DEPARTMENT OF TRANSPORT
AIRCRAFT CERTIFICATION
BRANCH
DAO # 01-O-01

APPROVED



BY: *[Signature]*
D. SHEPHERD (DE # 02)




DATE: 05.08.12
CERT. NO.: SH96-57
ISSUE NO.: #5

Copyright © 2005 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

DART

DESIGN RF	DRAWN BY RF	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED 	APPROVED 	DRAWING NO. DSI 9300	REV. B SHEET 4 OF 6
DATE 05.08.12		TITLE SIMPLEX TANK STEP	SCALE NTS



DETAIL W
DRILL $\varnothing 0.257$ THRU,
TOUCH UP WITH
ALODINE 1200 OR 1201
PER MIL-C-5541 AS SHOWN

SHOP COPY
RETURN TO
ENGINEERING
(-021/-022 STEP)
UNCONTROLLED COPY
SUBJECT TO AMENDMENT
WITHOUT NOTICE
WORK ORDER
NO. **32508**
VIEW R-R
NOT TO SCALE


CANADA DEPARTMENT OF TRANSPORT AIRCRAFT CERTIFICATION BRANCH DAO # 01-O-01	
APPROVED 	
BY:	D. SHEPHERD (DE # 02)
DATE:	05.08.12
CERT. NO.:	SH96-57
ISSUE NO.:	#5

Copyright © 2005 by DART AEROSPACE LTD


THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

DART

DESIGN RF	DRAWN BY RF	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED <i>[Signature]</i>	APPROVED <i>[Signature]</i>	DRAWING NO. DSI 9300	REV. B SHEET 5 OF 6
DATE 05.08.12		TITLE SIMPLEX TANK STEP	SCALE NTS



DETAIL V
NOT TO SCALE



(-023/-024 STEP)

VIEW X-X
NOT TO SCALE

SHOP COPY
RETURN TO
ENGINEERING
UNCONTROLLED COPY
SUBJECT TO AMENDMENT
WITHOUT NOTICE
WORK ORDER
NO. 32508

CANADA
DEPARTMENT OF TRANSPORT
AIRCRAFT CERTIFICATION
BRANCH
DAO # 01-O-01

APPROVED

BY: *[Signature]*
D. SHEPHERD (DE # 02)



DATE: 05.08.12
CERT. NO.: SH96-57
ISSUE NO.: #5

Copyright © 2005 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.

DART

DESIGN RF	DRAWN BY RF	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED <i>[Signature]</i>	APPROVED <i>[Signature]</i>	DRAWING NO. DSI 9300	REV. B SHEET 6 OF 6
DATE 05.08.12		TITLE SIMPLEX TANK STEP	SCALE NTS



CANADA
DEPARTMENT OF TRANSPORT
AIRCRAFT CERTIFICATION
BRANCH
DAO # 01-O-01

APPROVED

BY: *[Signature]*
D. SHEPHERD (DE # 02)

DATE: 05.08.12
CERT. NO.: SH96-57
ISSUE NO.: #5

Copyright © 2005 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.